BANGALORE DISTRICT.

Notice dated 29th May 1928.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Bangalore, St. Martha's Hospital Compound, Bangalore, up to 3 P.M. on the 25th June 1928, for sinking a well at Channapatna.

2. An approximate estimate of quantities is given below. These quantities are not guaranteed.

2. The plans, detailed estimate, etc., may be seen in the office of the President, District Board, Bangalore, between the hours of 12 A.M. to 5 P.M., on office days. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed and in no case the indefinite rate such as "so many per cent less" will be accepted. The value of each item must be worked out according to the rates tendered. Tenders not conforming to this rule will be rejected.

4. Each tender must be accompanied by a deposit of Rs. 150 (rupees one hundred and fifty) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for ....." in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President of the District Board, Banagalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

6. The name of the successful competitor, whose tender has been accepted, will be notified on the Notice Board in the District Board President's Office in due course. No enquiries regarding the acceptance or rejection of any tender will receive any reply.

7. Within eight days of the acceptance or rejection of the tender the successful competitor will be required to execute the usual contract bond on stamped paper in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The contractor shall complete the work by the end of September 1928. The President of the District Board will be competent to levy a fine not exceeding Rs. 50 for any infringement of the terms of the contract or for bad work or belated progress. If the contractor ceases or fails to abide by the terms of this notice or contract at any time during the currency thereof, he shall forfeit the security money to the District Board and also be bound to make good to the District Board any loss which may arise from such cessation or failure.

"FORM"

Approximate quantity of work for sinking a well in Channapatna.

Items of work	Approximate quantity	Unity	Tender rate at which each work will be worked out
			Rs. a. p.
1. Deepening well 0′ to 18′ deep. Hard soil ...	96	C.yd.	
2. Do ordinary chattu soil 18′ to 36′ ...	79	,,	
3. Do soft rocky soil 36′ to 48′ ..	44	,,	
4. Do blasting rock 48′ to 60′ ...	9	,,	
5. Do blasting rock 60′ to 78′ ..	11	,,	
6. Do newstone work with bond stones etc., complete average two miles lead.	3.456	C.ft.	
7. Burnt stone slabs 4″ and 6″ thick, roughly dressed and complete.	640	S.ft.	
8. Burnt brick in mortar	110	C.ft.	
9. Plastering with mortar	200	Sqr.	
10. Cement pointing	228	,,	
11. Jungle wood work. Beams	3	C.ft.	
12. Wooden pulley with iron fitting	3	each	
13. Bailing water	Lump	sum	
14. Unforeseen items, while execution found necessary including cutting holes in stone pillars and reconstructing top.	Lump	sum	

B. A. RAHMON,
President, District Board.